

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,
No.BBMP/EE/DD/Ten/01/2015-16, Date:04.01.2016

Indent No.20404

SCHEDULE-B

NAME OF WORK: Improvements to cross roads at Munikondappa layout link road shivappa garden to Dodda Maranna layout in Bagalagunte Ward no.14

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor R NAGARAJ		
				In Figures (Rs.)	In Words (Rs.)	Cont. AMOUNT
1	2	3	4	5	6	7
1	Scarifying kankar / gravel / metal crust upto 150mm thick with pick axes and disposal of stuff including cost of all labour charges Complete as per specifications	Sqm	622.5	24.0	Rupees Twenty Four Only	14940.00
2	Construction of embankment with approved material Gravel/Murum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications. (which includes cost of gravel / murum, watering charges & compaction by vibratory roller)	Cum	280.13	293.0	Rupees Two Hundred Ninety Three Only	82078.09
3	For Grading I material construction of granular sub-base by providing coarse graded crushed stone aggregates of Granite/ trap/basalt material spreading in uniform layers with motir grader on prepared surface mixing by a mix in place method with rotawater at OMC, and Compacting with vibratory roller to achieve the desired density, complete as per specifications. by mix in a Place method for course Graded Granular Sub Base Material as per 400-2 for grading I material .	Cum	62.25	1374.0	Rupees One Thousand Three Hundred Seventy Four Only	85531.50
4	Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. Specification No. 406 with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work	Cum	204.5	1611.0	Rupees One Thousand Six Hundred Eleven Only	329449.50

Nagaraj R

Signature of the Contractor

[Signature]
Executive Engineer

5	Providing and applying primer coat with S.S. Bitumen emulsion on prepared surface of granular base such as WBM, WMM including clearing of road surface and spraying primer at the rate of 0.6 kg / sqm using mechanical means complete as per specifications, with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.	Sqm	1022.5	30.0	Rupees Thirty Only	30675.00
6	Providing and laying bituminous concrete with hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder and filter transporting the hot mix to work site laying with paver finisher to the required grade, level and alignment. rolling with smooth wheeled vibratory and tandem rollers to achieve the desired compaction as per MORTH Specification clause no 500.9 complete in all respects complete as per specification no 509. using 40/60 TPH Capacity H.M.P With Mechanical paver Gr-II (30 mm to 45 mm) with 6% VG-30 Bitumen	Cum	40.9	9233.0	Rupees Nine Thousand Two Hundred Thirty Three Only	377629.70
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	93.38	79.0	Rupees Seventy Nine Only	7377.02
Total Percentage						927680.81 6.06%

Nagesh R

Signature of the Contractor

[Signature]
Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engineer